

BRUHATH BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of Work : Improvements to roads at Widia School Compound Road & C Narayana Layout in Bagalagunte in Ward No: 14

Sl. No	Description	Unit	Qty	Rates	
				In Figs	In Words
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 metres and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	1618.10	170.92	Rupees one hundred seventy and ninety-two paise only
2	Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occurring during rolling including cost of all labour, HOM of machinery complete as per specifications	Sqm	5393.65	5.30	Rupees five and thirty paise only
3	Providing, laying, spreading and compacting graded stone aggregates to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications	Sqm	1240.54	1768.08	Rupees one thousand, seven hundred sixty-eight and zero eight paise only
4	Providing and applying primer coat with SS bitumen emulsion on prepared surface of granular Base such as WBM, WMM including clearing of road surface and spraying primer at the rate of 0.60 kg/sqm using meachanical means complete as per specifications.	Sqm	5393.65	27.56	Rupees twenty-seven and fifty-six paise only


EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

EXECUTIVE ENGINEER - 4
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Division, Bangalore-571


Signature of the Contractor


Executive Engineer
Dasarahalli Division

No	Description	Unit	Qty	Rates	
				In Figs	In Words
5	Providing and laying bituminous macadam on prepared surface with crushed coarse aggregates as per design mix formula for base/binding course including loading of aggregates with F.E. loader, hot mixing of stone aggregates and bitumen in hot mix plant, transporting the mixed material in tipper to paver and laying mixed materials with paver finisher to the required level and grade, rolling by power roller to achieve the desired density, but excluding cost of primer / tack coat including lead, lift and cost of all materials, labour, HOM of machineries complete as per specification. MORTH Chapter 5 using 40/60 TPH capacity H.M.P. with Mechanical paver Gr-I (80mm to 100mm) with 3.1% VG-30 Bitumen	Cum	87.17 95.30	5605.28 5127.22	Rupees five thousand, one hundred twenty-seven and twenty-two paise only
6	Providing and applying tack coat using 80/100 grade bitumen (VG10) on the prepared black topped surfaces at 2.5 kg per 10 sqm heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications.	Sqm	5393.65	11.66	Rupees eleven and sixty-six paise only
7	Providing and laying bituminous concrete 40mm thick with hot mix plant, using crushed aggregates of specified grading, premixed with bituminous binder and filler, transporting the hot mix to work site, laying with a paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH specification clause No.500.9 complete in all respects complete as per specifications. MORTH Specification No.509. using 40/60 TPH capacity HMP with Mechanical paver Gr-I (50 to 65mm) with 5.5% VG-30 Bitumen	Cum	145.20 161.81	7858.84 7052.18	Rupees seven thousand, fifty-two and eighteen paise only
8	Conveying Excavated Earth to a lead of 10 Kms including loading & unloading charges by private Vehicle	Cum	1618.10	100.00	Rupees one hundred only


EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

4 ms (Four)
NO of Corrections


EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara Palike
Dasarahalli Division, Bangalore-560057


EXECUTIVE ENGINEER -
Bruhat Bangalore Mahanagara Palike,
Dasarahalli Division, Bangalore-57

Signature of the Contractor

Executive Engineer
Dasarahalli Division